

SCOPE OF WORK GREEN TREE EAST
SCHOOL INSTALLATION OF NEW
PLAYGROUND EQUIPMENT REQUEST FOR
PROPOSAL
VICTOR ELEMENTARY SCHOOL DISTRICT

1. MOBILIZE EQUIPMENT AND MATERIALS

- The scope of work for this project shall include the removal of playground equipment and the installation of a new complete playground structure. This project includes new “Pour-in-Place rubberized play surface” (see attached map drawings and specifications).

2. DEMO AND DISPOSE OF EXISTING EQUIPMENT (NOT IN THE SCHOOL DUMPSTERS)

- Contractor will remove old play surface and old play equipment and install new playground equipment and new rubberized play surface as specified in the plans and specifications. (see attached map drawings and specifications).
- The contractor shall tear out all old play surface and all old equipment and dispose of properly.
- Demo and properly dispose of existing wood chips. Approximately 2,952 SQFT.
- Demo and properly dispose of existing ADA ramp.
- SWINGS TO REMAIN

3. LABOR AND MATERIAL REQUIRED FOR THIS PROJECT

- Provide, grade, and compact sub base materials. Approximately 2,952 SQFT.
- Construction of concrete ledge curb. Approximately 241 linear feet.
- Installation only of Miracle Recreation Equipment – refer to MREC drawing R0036_42914638523 to be installed per manufacturer’s specifications and by MREC certified installer.
- Provide and install Pour-in-Place rubber surfacing. Approximately 2,952 SQFT for an average CFH of 8’. 50/50 black and standard color with aromatic binder.

4. The contractor will provide a (1) one-year installation warranty.

SCOPE OF WORK GREEN TREE EAST
SCHOOL INSTALLATION OF NEW
PLAYGROUND EQUIPMENT REQUEST FOR
PROPOSAL
VICTOR ELEMENTARY SCHOOL DISTRICT

5. Contractor will coordinate work with Joe Pont, Director of Facilities for installation and inspections. 760-245-1691 ext. 12550
6. All work shall be held to the specifications provided unless the District agrees otherwise in writing.
7. **All work shall conform completely to the specifications provided in the contract.**