



Erickson-Hall Construction

**BID # 24-102**

PARK VIEW GRADING & CONCRETE  
VICTOR ELEMENTARY SCHOOL DISTRICT  
VICTORVILLE, CA

December 1<sup>st</sup>, 2023

**ADDENDUM – 02**

**PLANS & SPECIFICATIONS**

ITEM NO. 1 PROJECT MANUAL, SPECIFICATION SECTION- 001116 NOTICE INVITING BIDS

A. The bid deadline remains 2:00:00 o'clock PM on the **7<sup>th</sup> day of December 2023**. The location for receipt of Bids remains the District Office for Victor Elementary School District, located at 12219 2<sup>nd</sup> Ave., Victorville, CA 92395.

**REQUESTS FOR CLARIFICATIONS**

ITEM NO. 2 Question: During the Job Walk held on November 30, 2023, it was noted that the new concrete to be placed would be required to be air-entrained. Please confirm air-entrained concrete requirement.

Response: All Bidders

Air-entrained concrete is required at all locations where new concrete will be placed. The bid package contractor shall include the standard air-entraining admixture per manufacturer specifications.

ITEM NO. 3 Question: On the site plan in the Project Manual, the new concrete to be placed at Portables A & B is noted to be 5' wide. During the job walk, it was noted that the new concrete at this area is to match existing at 8' wide. Please confirm the new concrete width at Portables A & B.

Response: All Bidders

New concrete at Portables A & B to match existing concrete width at 8' wide.

ITEM NO. 4 Question: Please provide clarification on what is to be done with the existing door thresholds.

Response: All Bidders

Bid package contractor shall remove and reinstall existing door thresholds.



Erickson-Hall Construction

ITEM NO. 5 Question: Please advise if bid package contractor shall include cost to remove existing irrigation where grading occurs, and new concrete is to be placed.

Response: All Bidders

Bid package contractor shall coordinate with District M&O to identify areas where existing irrigation will require alteration. The District M&O team will make alterations as required. The bid package contractor shall be responsible for repairing any existing irrigation lines that may get damaged during construction in the areas where this scope of work applies.

ITEM NO. 6 Question: Please provide clarification on who is responsible for touch-up paint on the existing buildings where concrete is noted to be removed and replaced.

Response: All Bidders

The bid package contractor shall be responsible for touch-up paint on the buildings as needed where the concrete is removed and replaced. The paint will be provided by the District.

END OF ADDENDUM 02